

SCOPE OF WORK

PRE-BID SITE VISIT: 5-22-18- 1:45 P.m

BID OPENING DATE: 5-21-18- 2:00 P.m

OCCUPANT: ELIZABETH L PERRYMAN

ADDRESS: 2950 EDGEWOOD ST

	QTY.	UNIT	PRICE	TOTAL
<u>ROOF:</u>				
REMOVE & DISPOSE OF ALL ROOFING & DEFECTIVE SHEATING, CUT 1" WIDE VENT AT RIDGE, REPLACE UP TO 16 SF OF DECKING PER 100 SF OF ROOF. USE PINE BOAD OR CDX PLYWOOD OF MATCHING THICKNESS, INSTALL EASY LAY UDL 15 SYNTHETIC UNDERLAYMENT, INSTALL PEEL & STICK IN ALL VALLEYS. INSTALL PREFORM WHITE ALUMINUM DRIP EDGE 26 GA. REPLACE ALL FLASHING & ALL VENT ALL VENT PIPE BOOTS, INSTALL NEW 25 YEAR SHINGLES. INSTALL UP TO 2 FT OF END OF RIDGE VENT. (CONTRACTOR IS RESPONSIBLE FOR MEASURING ROOF)	X.00	SQ	_____	_____

GRAND TOTAL: _____