

PREBID INSPECTION
 Tuesday, October 22, 2019 @ 10:00 a.m.
BIDS DUE
 Thursday, October 31, 2019 @ 2:00 p.m.

Address: 1071 LUBEL Avenue **Unit: Unit 01**

Location: 1 - OUTSIDE Approx. Wall SF: 0 Ceiling/Floor SF: 0

| Spec # | Spec | Quantity | Units | Unit Price | Total Price |
|--------|------|----------|-------|------------|-------------|
|--------|------|----------|-------|------------|-------------|

Trade: 15 Roofing

| | | | | | |
|---|--|-------|----|-------|-------|
| 1 | 4580 TEAR OFF AND REROOF SHINGLES Remove and dispose of all roofing & defective sheathing. Cut a 1" wide vent at ridge board. Replace up to 16 sf of sheathing per 100 sf of roof using pine board or CDX plywood of matching thickness. INSTALL NEW EASY LAY UDL SYNTHETIC UNDERLAYMENT (CONTRACTOR MUST SHOW DOCUMENTATION OF APPROVED EQUAL IF THEY WANT TO USE ANOTHER BRAND) Install preformed white aluminum, drip edge 26GA, REPLACE ALL vent pipe boots. Install a 220 lb fiberglass asphalt, 3 tab shingle with a 25 yr warranty. Replace all flashing. Install shingle-over ridge vent. INSTALL PEEL AND STICK IN ALL VALLEYS. CONTRACTOR IS RESPONSIBLE FOR MEASURING ROOF. | 23.00 | SQ | _____ | _____ |
|---|--|-------|----|-------|-------|

Trade: 22 Plumbing

| | | | | | |
|---|---|------|----|-------|-------|
| 2 | Custom R/R SEWER LINE OWNER SAY WHEN WIFE WASH CLOTHES WATER COMES UP IN TUB WHEN SHE RINSE, R/R SEWER LINE FROM STREET TO HOUSE WITH NEW PVC LINE. | 1.00 | EA | _____ | _____ |
|---|---|------|----|-------|-------|

Location Total: _____

Unit Total for 1071 LUBEL Avenue, Unit Unit 01: _____

Address Grand Total for 1071 LUBEL Avenue: _____

Bidder: _____