



To: Pre-Quote Meeting Attendees and Registered Plan holders

From: David M. Cordingly
City of Mobile Architectural Engineering Department

Re: MFRD Boat Lift & Dock Improvements
Project #FD-040-23

Date: July 18, 2023

This Addendum forms a part of, and modifies, the Request for Quotes for the above referenced project. Acknowledge the receipt of this Addendum No. 2 and all subsequent Addenda, if any, in the space provided on the Quote Form. Failure to do so may subject Contractor to disqualification.

General:

Item #1

Boat lift bunk boards are to have synthetic bunk covers in lieu of carpeted.

Basis of Design: Gatorbak XP Synthetic Bunk Cover

Item #2

Additional electrical work is needed. The current electrical panel is not adequate for servicing the new boat lift. Install new 200-amp service from the transformer to the existing electrical panel (240-FT); upgrade existing electrical panel to a 200-amp breaker box; upgrade wiring for the (2) existing boat lifts to tie into new panel; and wire the new boat lift to the upgraded panel.

Drawings: N/A

RFI's: N/A

Attachments:

1. N/A

END OF ADDENDUM NO. 2