

February 11, 2021

TRAFFIC SIGNAL AND ITS UPGRADES ALONG GOVERNMENT STREET (US HIGHWAY 98)
WITHIN THE CITY OF MOBILE
STPMB-HSIP-0016(525)
PROJECT NO: 2018-2060-06

ADDENDUM NO. 3

BID DATE: FEBRUARY 17, 2021
2:30 p.m.

A copy of this Addendum No. 3, signed by an authorized representative of this contractor, must be attached or bound in the front of the Contract Documents and Specifications. **Contract Documents and Specifications along with Addendum No. 3 must be submitted together to the City of Mobile or the contractors bid shall be declared invalid.**

I, the undersigned, hereby acknowledge receipt of this addendum and certify to the City of Mobile that I understand the information attached hereto and have made the appropriate adjustment to the bid proposal.

Authorized Representative of Contractor

Date

Contractor

The bid documents for Project No. 2018-2060-06 Traffic Signal and ITS Upgrades along Government Street (US Highway 98) within the City of Mobile are hereby revised as follows:

Contract Document – Item IV Proposal (Bid)

Amend last paragraph on Page 20 to change the last date for questions to February 15, 2021.

PLAN SHEET 2 – Traffic Signal Plan Notes

Amend note 532 as follows:

532. ALL RADAR DETECTION SHALL BE WAVETRONIX SMARTSENSOR MATRIX OR ADVANCED AS REQUIRED TO MEET DETECTION SETBACK.

February 11, 2021

PLAN SHEET 2 – Traffic Signal Plan Notes (cont.)

Add the following plan notes:

536. ANY REQUIRED ASPHALT OR CONCRETE RESTORATION AS A RESULT OF CONSTRUCTION ACTIVITIES SHOULD MATCH EXISTING OR AS OTHERWISE DIRECTED BY THE ENGINEER. REPAIR AND RESTORATION SHALL BE SUBSIDIARY TO OTHER ITEMS.

PLAN SHEET 2A – Intelligent Transportation Systems (ITS) Plan Notes

Add the following notes:

1145. LOCATE TONE WIRE NEED ONLY BE GROUNDED IN COMM BOXES THAT CONTAIN SPLICES.
1146. CONCRETE COLLARS WILL NOT BE REQUIRED FOR COMM BOXES.
1147. PAYMENT FOR 729 PAY ITEMS SHALL BE MADE IN INCREMENTS OF:
- UP TO 70% OF THE CONTRACT UNIT PRICE UPON SUCCESSFUL COMPLETION OF THE BENCH TEST AND INSTALLATION OF ITEM(S) [PARTIAL PAYMENTS MAY BE MADE IN ACCORDANCE WITH ARTICLE 109.07 UP TO THIS PERCENTAGE.]; AND,
 - ADDITIONAL 15% OF THE CONTRACT UNIT PRICE UPON COMPLETION OF THE FIELD TEST; AND,
 - FINAL 15% OF THE CONTRACT UNIT PRICE UPON COMPLETION OF THE ACCEPTANCE TEST (BURN-IN).

PLAN SHEET 3A – Summary of Quantities

Delete Pay Item 734G-100 SPLICE CLOSURE, UNDERGRADE, 12 FIBER in the Required ITS Pay Items table. The quantity was duplicated and included in the same table as Pay Item 729N-114, MISC INFRASTRUCTURE, SPLICE ENCLOSURE, UNDERGROUND 48F.

CLARIFICATION: Pay Item 729N-550 MISCELLANEOUS INFRASTRUCTURE, POWER OVER ETHERNET (POE) EXTENDER - OUTDOOR in the Required ITS Pay Items table is not a separate item. Per Note 1 on Sheet 29 of the plans, this item is subsidiary to Pay Item 729D-1001 CCTV CAMERA, POSITIONER (TYPE A).